EQUIPMENT ANCHORAGE & SEISMIC ENGINEERING www.EquipmentAnchorage.com

ICW USA INC.

DES. J. ROBERSON

2/17/17


11-1532 JOB NO.

DATE

SHEET

SHEETS

ULTRA II ARTICULATING WALL MOUNT



NOTES:

FORCES ARE DETERMINED PER 2016 CALIFORNIA BUILDING CODE AND ASCE 7-10.


STRENGTH DESIGN IS USED. (Sps = 1.70, $a_p = 2.5$, $l_p = 1.5$, $R_p = 2.5$, z/h < 1)

HORIZONTAL FORCE (Eh) = 3.06 Wp VERTICAL FORCE (Ev) = 0.34 Wp

2. CENTER OF GRAVITY (C.G.) AND WEIGHT ARE THE GOVERNING PARAMETERS FOR DESIGN. THIS PREAPPROVAL ENCOMPASSES ALL WEIGHTS UP TO THE MAXIMUM WEIGHT SHOWN.

STEEL STUD WALL SECTION

3. STRUCTURAL ENGINEER OF RECORD FOR THE BUILDING SHALL PROVIDE SUPPORT STRUCTURE. DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.





www.EquipmentAnchorage.com

ICW USA INC.

DES. J. ROBERSON

11-1532

2

SHEET

ULTRA II ARTICULATING WALL MOUNT

DATE 2/17/17


JOB NO.

of 3 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

19" TRACK

<u>WALL MOUNTED</u>



ELEVATION AT WALL

LOADS: PER 2016 CALIFORNIA BUILDING CODE AND ASCE 7-10.

STRENGTH DESIGN IS USED (SDS = 1.70, &p = 2.5, |p = 1.5, Rp = 2.5, z/h < 1)

WEIGHT = 110 LB

HORIZONTAL FORCE (En) = 3.06 Wp = 337 LB

VERTICAL FORCE (Ev) = 0.34 Wp = 37 LB

SCREW FORCES:

TENSION (T) (AWAY FROM WALL)

$$T_{u \text{ VERTICAL}} = \frac{(1.2(110\#) + 37\#)26.91"}{2 \text{ SCREWS}} = 143 \text{ LB/SCREW}$$

Tu PARALLEL = 0 LB (FREE TO ROTATE)

$$T_{\text{U PERP.}} = \frac{337\#}{4 \text{ screws}} = 84 \text{ LB/SCREW}$$

$$T_{\text{UMAX}} = 143# + 84# = 227 LB/SCREW (MAX)$$

SCREW SPEC: 1/4" TEK SCREWS

 $\Phi T = 418 LB/SCREW$

 $\Phi V = 362 LB/SCREW$

TENSION (T) AT SHEAR MAX (AGAINST WALL)

$$T_{\text{u VERTICAL}} = \frac{(1.2(110\#) + 37\#)4"}{2\text{screws}(16")} = 21 \text{ LB/SCREW}$$

$$T_{u} PARALLEL = \frac{337\#(4'')}{8 screws (1.25'')} = 135 LB/SCREW$$

$$T_{\text{UPFRP}} = 0 \text{ LB}$$
 (FREE TO ROTATE)

$$T_{IIMAX} = 21# + 135# = 156 LB/SCREW (MAX)$$

SHEAR (V)

$$V_{u \text{ MAX } \bullet \text{ T } u \text{ MAX}} = \sqrt{\left(\frac{1.2(110\#) + 37\#}{8 \text{ screws}}\right)^2 + \left(\frac{337\#}{4 \text{ screws}}\right)^2} = 87 \text{ LB/SCREW (MAX)}$$

UNITY CHECK: (AGAINST WALL GOVERNS)

$$\left(\frac{\mathsf{Tu}}{\mathsf{\Phi}\mathsf{T}}\right) + \left(\frac{\mathsf{Vu}}{\mathsf{\Phi}\mathsf{V}}\right) \le 1.0 \quad \left(\frac{156}{418}\right) + \left(\frac{221}{362}\right) = 0.98 \le 1.0 \quad \text{°.} \quad \underline{\mathsf{O.K.}}$$



www.EquipmentAnchorage.com

ICW USA INC.

ULTRA II ARTICULATING WALL MOUNT

DES. J. ROBERSON

11-1532 JOB NO.


2/17/17

OF SHEETS

WALL MOUNTED

SEISMIC SUPPORTS & ATTACHMENTS





ELEVATION AT WALL

LOADS: PER 2016 CALIFORNIA BUILDING CODE AND ASCE 7-10.

STRENGTH DESIGN IS USED (SDS = 1.70, ap = 2.5, lp = 1.5, Rp = 2.5, z/h < 1)

WEIGHT = 110 LB

HORIZONTAL FORCE (En) = 3.06 Wp = 337 LB

VERTICAL FORCE (Ev) = 0.34 Wp = 37 LB

SCREW FORCES:

TENSION (T) (AWAY FROM WALL)

$$T_{u \text{ VERTICAL}} = \frac{(1.2(110\#) + 37\#)26.91"}{2 \text{ screws}(33")} = 69 \text{ LB/SCREW}$$

Tu PARALLEL = 0 LB (FREE TO ROTATE)

$$T_{\text{U PERP.}} = \frac{337\#}{4 \text{ screws}} = 84 \text{ LB/SCREW}$$

$$T_{u MAX} = 69# + 84# = 153 LB/SCREW (MAX)$$

TENSION (T) AT SHEAR MAX (AGAINST WALL)

$$T_{u} \text{ VERTICAL} = \frac{(1.2(110\#) + 37\#)4"}{2 \text{ SCREWS}(33")} = 10 \text{ LB/SCREW}$$

$$T_{u \text{ PARALLEL}} = \frac{337\#(4'')}{8 \text{ screws}(1.25'')} = 135 \text{ LB/SCREW}$$

$$T_{UMAX} = 10# + 135# = 145 LB/SCREW (MAX)$$

SHEAR (V)

$$V_{u MAX @ T u MAX} = \sqrt{\left(\frac{12(110\#) + 37\#}{8 \text{ screws}}\right)^2 + \left(\frac{337\#}{4 \text{ screws}}\right)^2} = 87 \text{ LB/SCREW (MAX)}$$

UNITY CHECK: (AGAINST WALL GOVERNS)

$$\left(\frac{\mathsf{Tu}}{\mathsf{\Phi}\mathsf{T}}\right) + \left(\frac{\mathsf{Vu}}{\mathsf{\Phi}\mathsf{V}}\right) \leq 1.0 \ \left(\frac{145}{418}\right) + \left(\frac{154}{362}\right) = 0.77 \leq 10 \ \text{.°.} \ \underline{\mathsf{O.K.}}$$